



### NOTES

1. WORK AND MATERIALS SHALL CONFORM TO THE "STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION", (GREEN BOOK).
2. CROSS SECTIONAL AREA=1.42 SQ. FT.
3. CONCRETE SHALL BE PER CITY OF REDDING CONSTRUCTION STANDARDS PAGE 100.00.
4. ALL BROOMING SHALL BE PARALLEL TO THE DIRECTION OF FLOW.
5. 1/2-INCH, PRE-MOLDED JOINT FILLER SHALL BE LEFT INSTALLED IN EXPANSION JOINTS AT THE 'BC' AND 'EC' OF ALL CURB RETURNS AND AT THE ENDS OF DRIVEWAYS AND SHALL BE HELD FIRMLY IN PLACE PRIOR TO PLACING CONCRETE.
6. CONTROL JOINTS SHALL BE 2-INCHES DEEP AND AT INTERVALS NOT TO EXCEED 16 FT. OC. TOP 3/4-INCH OF THE CONTROL JOINT SHALL BE FILLED WITH POLYURETHANE SEALANT (SIKAFLEX-1A OR EQUAL)

DWG DATE 10-10		SCALE: NTS	CITY OF YREKA DEPARTMENT OF PUBLIC WORKS	
		APPROVED BY <i>Steven D. Neill</i> STEVEN D. NEILL, P.E. DIRECTOR OF PUBLIC WORKS		CURB AND GUTTER INFILL AREAS
MARK	DATE	REVISION		